



Rafa Roofing - Lincoln NE
1830 Yolande Ave Lincoln
NE 68521
Phone: (402) 433-5425

Company Representative
Cesar Cervantes
Phone: (402) 381-2166
Cesar@rafarroof.com

Roofing Estimate

10/23/2024

Mike Kalkwarf
2429 County Road F
Crete, NE 68333
(402) 826-9766

Job: Mike Kalkwarf

Roofing Section

Front Elevation Section

- Remove (1) layer of existing Wood Shake shingle down to deck.
- Re-nail any loose sheeting - If bad or rotten wood is discovered, it will be replaced. (Price to be determine at time of install)
- Install new ice water shield
- Install new Metal Roof Pro Rib 26 gauge.
- Install New Rake Metal and Eave Metal
- Install H&R Metal
- Install Flashing if need
- will Reuse the existing top flashing between the top flat roof
- Measurement 69' W 52" H 329 sq with 10% waste

Left Elevation Section

- Remove (1) layer of existing Wood Shake shingle down to deck.
- Re-nail any loose sheeting - If bad or rotten wood is discovered, it will be replaced. (Price to be determine at time of install)
- Install new ice water shield
- Install new Metal Roof Pro Rib 26 gauge.
- Install New Rake Metal and Eave Metal
- Install H&R Metal
- Install Flashing if need
- will Reuse the existing top flashing between the top flat roof
- Measurement 28' W 52" H 137 sq with 10% waste

Right Elevation

- Remove (1) layer of existing Wood Shake shingle down to deck.
- Re-nail any loose sheeting - If bad or rotten wood is discovered, it will be replaced. (Price to be determine at time of install)
- Install new ice water shield
- Install new Metal Roof Pro Rib 26 gauge.
- Install New Rake Metal and Eave Metal
- Install H&R Metal
- Install Flashing if need
- will Reuse the existing top flashing between the top flat roof
- Measurement 69' W 52" H 137 sq with 10% waste

\$6,030.00

Note:

Notes

THIS PROPOSAL IS VALID FOR 30 DAYS.

Any additional sheeting, if needed, will be done at \$100.00 per sheet.

Any additional unforeseen layers of shingles will be removed at the cost of \$20 per square (\$30 per square if Wood shake Shingles), per layer.

Any loose hanging items should be removed from wall prior to any work being done on roof.

Payments.

A down payment of \$1 of the total contract amount is due before work is to begin, the remainder shall be due upon completion.

Customer has as period of three business days to pay the amount due in full.

Failure to make timely payment will result in charges added to the overdue amount at the lesser of 20% per annum (3% per month) or the maximum charge allowed by law, whichever is less.
Customer agrees to pay all collection costs, including court, legal, and attorneys' fees incurred in the collection of past due amounts

Company Authorized Signature

Date

Customer Signature

Date

Customer Signature

Date