



# TCC Corporation

6820 Powell St  
Loveland, CO 80538

# REQUEST FOR CHANGE

No. 3

Phone: 970-460-0583

Fax: 970-460-0871

TITLE: Retaining Wall

DATE: 05/28/2025

PROJECT: Dundy County Tiger Tots

JOB: 2503

TO: Todd Boldt  
Wilkins ADP  
2204 University Drive  
Kearney, NE 69021

CONTRACT NO:

*\* approved at the June  
24-25 Regular Board  
Meeting*

## DESCRIPTION OF REQUEST

Change Order to excavate and pour approximately 130'-0", 8'-0" tall wall with a 2'-0" wide footing on the south side of the new building. The grade falls steeply to the baseball field. The currently budgeted chain link fence will be installed within the interior side of the retaining.

Description	Amount
Excavate, form, pour, approximately 130'-0", 8'-0" tall wall along south side of the building. Including concrete pump truck.	\$32,650.00
General Conditions	\$3,070.00
General Liability Insurance	\$142.05
Builder's Risk Insurance	\$259.76
Bond	\$893.00
Contractor's Fee	\$3,572.19

<b>Total</b>	<b>\$40,587.00</b>
--------------	--------------------

## APPROVAL:

By: \_\_\_\_\_  
Todd Boldt

By: \_\_\_\_\_  
Brian Crownover

Date: \_\_\_\_\_

Date: \_\_\_\_\_

# Doolittle Concrete

33755 Rd 763  
Madrid, NE 69150

## Estimate

Date	Estimat...
5/26/2025	2437

Name / Address		Project	
TCC corporation		8ft wall on south side of new building	
Item	Description	Qty	Total
8' Poured wall	Cost to pour 130' of 8' tall wall 12" wide with 2' wide footing on south side of new building.	130	30,550.00
Pumper truck	Cost of pumper truck for walls.	12	2,100.00
<b>Total</b>			\$32,650.00



# Doolittle Concrete

33755 Rd 763  
 Madrid, NE 69150

## Estimate

Date	Estimat...
5/26/2025	2437

Name / Address		Project	
TCC corporation		8ft wall on south side of new building	
Item	Description	Qty	Total
Excavating	Machine time and labor to remove dirt on to place walls	30	2,400.00
8' Poured wall	Cost to pour 130' of 8' tall wall 12" wide with a 2' wide footing on south side of new building.	130	30,550.00
8' Poured wall	Cost to pour 75' of 8' tall wall 12" wide with a 2' wide footing on east side of new building	90	21,150.00
Pumper truck	Cost of pumper truck for walls.	12	2,100.00
Travel expense.	Travel expense from Madrid to	80	960.00
<b>Total</b>			\$57,160.00

**TCC Corporation**  
 6820 Powell Street  
 Loveland, Colorado 80538



1801 North 98th Street  
 Lincoln, NE 68505  
 Ph: 402-580-9698

**DATE** July 2025  
*Quotation valid until:* August 2025

## Estimate for Landscaping

	Estimated Project Costs	Check Options/ Zones to be Included in Initial Project
<b><u>TIGER TOTS CHILD CARE RETAINING WALL - BENKELMAN, NEBRASKA:</u></b>		
<ul style="list-style-type: none"> <li>❖ Excavation of area for installation of retaining walls (<i>see accompanying landscape plan for specifics</i>),</li> <li>❖ Construction of base using 1/4" white rock chips,</li> <li>❖ Compaction of base using jumping jack and/or hand tampers,</li> <li>❖ Construction of walls using 10D Anchor wall block- Chestnut <i>to attempt match stone provided on specs</i> ),</li> <li>❖ Installation of perforated drain tile on back side of walls with 6" x 6" drains through the block to assist in water drainage and</li> <li>❖ Installation of top soil behind walls to meet necessary grade,</li> <li>❖ Installation of caps.</li> </ul>		
<b><i>Sub-total for South &amp; East Walls</i></b>	\$ 172,480.00	

	<b>TOTAL</b>	\$ 172,480.00
	<b>Plus: 7% Sales Tax</b>	\$ 12,073.60
	<b>GRAND TOTAL</b>	\$ 184,553.60
<b>Initial Payment Due (1/2):</b>		\$92,276.80
<b>Final Payment Due Upon Completion of Project (1/2):</b>		\$

**TCC Corporation**  
6820 Powell Street  
Loveland, Colorado 80538



**TERMS:**

- \* One-half of total project cost is due upon scheduling of work.
- \* If paying with credit card a 3.5% processing surcharge will be added to the grand total.
- \* \$50.00 (*plus parts*) for moving of each automatic sprinklers.
- \* Price assumes plans and specs provided by contractor are accurate.
- \* Price does not include removal or disposal of concrete footings or other obstructions below grade, may incur additional costs.
- \* Property owner responsible for flagging of all sprinkler heads.
- \* Price does not include damage to existing drip system and/or re-installation of necessary lines.
- \* Prices effective for 30 days following submission of original estimate.
- \* Accounts not paid upon completion will be considered past due and be assessed a 1.5% monthly finance charge.
- \* If necessary, Creative Landscaping will contact all major utilities. We are not responsible for underground sprinkler systems, dog fences, unmarked gas grill lines, outdoor lighting lines, pool lines and other lines that may be underground including drain tile. Additionally, we will not be held responsible for any utility lines that are less than 8 inches deep in the ground.

Approved by:
_____
<i>(Customer's Signature)</i>
Date: _____
_____
<i>(Creative Landscaping)</i>
Date: _____

We would sincerely appreciate the opportunity to work with you on this important project to enhance the value of your home. Should you have any questions and/or if we can be of additional assistance, please don't hesitate to call us at any time. We look forward to hearing back from you soon as to the next steps!

Best regards,

Tyler Thille  
(402) 580-4451

Dexter Lambie  
(402) 560-8008

*Visit us on the Web at [www.creative-landscaping.com](http://www.creative-landscaping.com)*