

6 Year Plan 2026 - 2032
Crete, Nebraska

PRIORITY NO.	PROJECT NO.	DESCRIPTION	TOTAL ESTIMATED CONSTRUCTION COST	GENERAL OBLIGATION COST
1	312	Main Avenue BNRR North Side to Linden Avenue BNRR South Side Construct Viaduct 30' 9" P.C. concrete with 10' Pedestrian walkway over BNRR Tracks - Includes Relocation Expenses	\$31,874,000	\$3,187,400
2	288	Tuxedo Park Bridge to Tuxedo Park Walk Bridge Construct 350' 5" P.C. concrete 8' trail walkway/bikeway	\$94,900	\$94,900
3	272	In Westwoods subdivision Remove and reconstruct entire roadway 32' wide 7" P.C. concrete paving with curb and gutter, 5' sidewalks & re-compact and reset manholes to grade	\$3,206,340	\$1,500,000
4	265	On East 13th Street, from Jasmine Avenue to East City Limits Remove existing concrete; construct 9" P.C. concrete paving 32' wide with 5' sidewalks	\$1,029,830	\$350,000
5	271	On North Main Avenue, from BNRR tracks to 24th Street Mill and overlay 2" asphalt 24' wide from existing edge including intersection approaches.	\$515,920	\$515,920
6	290	West 12th Street west of Arizona Avenue Construct 9" P.C. concrete 25' wide 825' long	\$483,650	\$0
7	301	On East 15th Boswell Avenue to Iris Avenue Remove existing concrete; construct 7" P.C. concrete paving 32' - 41' wide with 5' sidewalks	\$2,000,000	\$892,526
8	282	On 21st Street from Linden Avenue to Kingwood Avenue Construct 7" P.C. concrete paving 32' wide with storm sewer	\$217,440	\$125,000
9	208	On 20th Street, from Linden Avenue to Kingwood Avenue #9 Construct 7" P.C. concrete paving 32' wide with storm sewer	\$303,160	\$150,000