

6 Year Plan 2024 - 2030  
Crete, Nebraska

PRIORITY NO.	PROJECT NO.	DESCRIPTION	TOTAL ESTIMATED CONSTRUCTION COST	GENERAL OBLIGATION COST
1	272	In Westwoods subdivision  Remove and reconstruct entire roadway 32' wide 7" P.C. concrete paving with curb and gutter, 5' sidewalks & re-compact and reset manholes to grade	<b>\$3,206,340</b>	\$1,500,000
2	265	On East 13th Street, from Jasmine Avenue to East City Limits  Remove existing concrete; construct 9" P.C. concrete paving 32' wide with 5' sidewalks	<b>\$1,029,830</b>	\$350,000
3	271	On North Main Avenue, from BNRR tracks to 24th Street  Mill and overlay 2" asphalt 24' wide from existing edge including intersection approaches.	<b>\$515,920</b>	\$515,920
4	290	West 12th Street west of Arizona Avenue  Construct 9" P.C. concrete 25' wide 825' long	<b>\$483,650</b>	\$0
5	278	On Linden Avenue, from 20th to 21st Avenue  Construct 7" P.C. concrete paving 32' wide with storm sewer	<b>\$308,330</b>	\$155,000